

Dr Challoner's Grammar School, Amersham



Constant Air Systems Ltd undertook the replacement of the heating system at Dr Challoner's Grammar School. All works were completed during the summer shut down with Constant Air Systems Ltd acting as the principal contractor.

This involved the installation of the following:

- 2 No. Boiler plantroom re-fits to replace existing oil fired boilers with gas fired.
- Distribution pipework to Science / Tower block and Sixth Form / Main Teaching Block
- Replacement of existing radiators and fan coil units with new
- Removal of existing feed & expansion tank to allow mains fed system
- New BMS system including all electrical wiring
- General removals of redundant pipework & equipment and builders work in conjunction.

The total contract value was circa £495,000