## **Illustration of Asbestos Work Categories**

Loose fill lagging insulation

Lagging and sprayed insulation

Asbestos insulation – if significant work that exceeds the control limit

Loose dust & small pieces of debris (gross contamination)

Asbestos insulating board (AIB) – if significant work that exceeds the control limit

Asbestos insulation/ AIB – if short duration work below control limit and removal work not part of maintenance

Textured decorative coatings – using gels/steam to for large-scale removal

Paper, felt and cardboard e.g. electrical equipment insulation, ropes and yarns or cloth, or gaskets and washers – depending on condition – if poor condition or degraded during work NNLW, if kept virtually intact non-licensed

AIB – if short duration work below control limit and part of maintenance work

Textured decorative coatings – only when carefully cutting around backing sheets to achieve removal intact

Strings kept virtually intact e.g. removed whole

Resin-based materials e.g. friction products/brake lining

Conveyor belts/ drive belts

**Asbestos cement products** 

Thermoplastic/vinyl floor tiles, bitumen roof felt shingles, asbestos paper damp proof coatings, mastics, asbestos paper backed PVC floors, resurfaced PVC panels & compounds

HSF

Licensed Asbestos Work

Notifiable Non-Licensed Asbestos Work

Non-Licensed Asbestos Work

Low fibre release when disturbed = lower risk work

High

fibre

release

when

disturbed

= higher

risk work