PREFABRICATED PACKAGED BOILER PLANTROOM

CASE STUDY

Gatwick Airport - North Terminal




Value £150,500
Build period 12 weeks
Client SPIE


Contents:

- ✓ Weatherproof enclosure 6.0 x 3.7 x 3.0 metres high
- 2no.off Hamworthy MTHW boilers model Ansty
- ✓ Flue system through roof
- Circulating twin head pumps
- Pressurisation unit c/w 300 litre expansion vessel
- 100mm dia Combined air & dirt separator
- Chemical dosing pot
- ✓ MTHW Heating flow & return, & cold water services.
- Thermal insulation & protective cladding
- Internal lighting, emergency lighting, & small power
- ✓ BMS Controls & wiring

See reverse for schematic arrangement and general layout.

Constant Air Systems Limited





Constant Air Systems Limited