

Case Study: 17842 Sikalastic Low Level Roof Refurb



Value
£3,988



Location
Physio Therapy, Heatherwood Hospital, Ascot



Contract Length
3 days



Types of Work Involved:

Sikalastic – 618 liquid coatings

The Task:

To re-furbish a low level flat asphalt roof.

The Problem:

Water ingress into the building through the failed Asphalt roof surface.

The Solution:

Adamson Construction erected scaffolding access tower and full edge protection. The roof surface was cleaned with Sika Biowash to kill all fungal growth. Small local repairs were carried out and existing sub-standard repairs were removed.

The first coat of Sikalastic – 618, 1.5L/m² was the applied before the dressing of the Sika Ree-mat into embedment coat whilst wet.

This was allowed to set and then the second coat was applied at 0.75L/m², making sure that all pinholes were filled.

The job was signed off and the edge protection was carefully removed.

THE JOBS FINISHED
WHEN THE
CLIENTS SATISFIED,
NOT US.