

HOW IT WORKS

'When-in-Area' Servicing reduces costs by saving money on the technician's travel time: you pay one fixed competitive rate which covers travel and the first hour spent on site – generally su fficient for a normal service.

WHAT IS INCLUDED IN THE "WIA" SERVICE

- ALL TRAVEL COSTS
- THE FIRST HOURS LABOUR TIME

ANY SPARE PARTS REQUIRED ARE CHARGED ADDITIONALLY

WHAT WORK IS CARRIED OUT?

- Clean and Inspect Developer Tank, cleaning chemicals used where necessary
- Clean and Inspect Fixer Tank cleaning chemicals used where necessary
- Clean and Inspect Water Tank cleaning chemicals used where necessary
- Check Developer Module for correct gear operation and film transport
- Check Fixer Module for correct gear operation and film transport
- Check Water Module for correct gear operation and film transport
- General inspection of all machine components and advise if parts need replacing
- Check Developer Tank temperature
- Check Fixer Tank temperature
- Test tank Thermistors
- Check operation of tank solenoid (where fitted)
- Check Fan Unit for free rotation and remove any accumulated dust
- Carry out Earth Continuity Test
- Carry out Vischeck film quality control test
- Issue Manufacturer's Certificate of Conformity, assuming that parts that require changing have been replaced



E-mail:owen@velopex.com or andy@velopex.com