
#### 1. Undercarriage:



7 Point Under

Solid plate/ Support beams not visible.





#### 1. Undercarriage:



7 Point Under

432 lbs. of cocaine!





#### 2. Outside/Inside Doors:

- Secure and reliable locking mechanisms
- Look for different color bonding material
- Loose Bolts
- Plates and repairs



7 Point Doors





#### 2. Outside Doors:



7 Point Doors

Rivet type & color/ New & old rivets together.





#### 2. Outside Doors:



7 Point Doors

Detachable or loose bolts can allow access inside container.





#### 2. Inside Doors:



7 Point Doors

Chemicals are used to make bolts look old and rusty.





#### 2. Inside Doors:



7 Point Doors

Non-factory putty keeps bolts in place.





#### 2. Inside Doors:



7 Point Doors

Solid plates should not cover standard container cavities.





#### 2. Inside Doors:



7 Point Doors

Container cavities. Five container shipment/837 lbs. of cocaine.





#### 3 & 4. Right/Left Sides:

- Unusual repairs to structural beams.
- Repairs to the walls on the inside of the container must be visible on the outside.
- Use tool to tap side walls. Listen & feel for hollow sound!



7 Point Sides





3 & 4. Right/Left Sides:



7 Point Sides

17 Container Shipment/ 1,275 lbs. of cocaine





#### 3 & 4. Right/Left Sides:



7 Point Sides

55 lbs. of cocaine/ One beam!





#### 5. Front wall:

- Blocks and vents are visible.
- Use tool to tap front wall. Listen and fell for hollow sound!
- Range finder, measuring tape and/or string can be utilized to determine the length of container.



7 Point Wall





#### 5. Front wall:



7 Point Wall

Use laser range finder from door opening.





#### 5. Front wall:



7 Point Wall

Normal block and air vent





#### 5. Front wall:



7 Point Wall

Short distance between block and vent. Wall colors are different!





#### 5. Front wall:



7 Point Wall

Fake block made out of cardboard!





#### 5. Front wall:



7 Point Wall

Real block concealed behind false wall.





#### 5. Front wall:



7 Point Wall

1,290 lbs. Marijuana. Range finder used.





#### 6. Ceiling/Roof:

- Ceiling is a certain height from floor. Blocks & vents are visible.
- Uncomfortable feeling inside container.
- Repairs to the ceiling on the inside of the container should be visible on the outside.
- Use tool to tap ceiling. Listen for hollow sound.









#### 6. Ceiling/Roof:



7 Point Ceiling

One row of vent holes visible.





#### 6. Ceiling/Roof:



7 Point Ceiling

Blocks are not visible.





6. Ceiling/Roof:



7 Point Ceiling

1,200 lbs. of cocaine!





#### 7. Floor:

- Floor should be a certain height from the ceiling
- Floor should be flat. Do not need to step up to get inside!
- Different floor heights
- Unusual repairs



7 Point Floor





#### 7. Floor:



7 Point Floor

Step up to get inside! Why?





#### 7. Floor:



7 Point Floor

Sloppy repairs and welding.





#### 7. Floor:



7 Point Floor

Welded steel plates/1,300 lbs. of cocaine underneath the plates!





#### 7. Floor:



7 Point Floor

False compartment/ 550 lbs. of cocaine within compartment!





# Container Inspection...

#### **17-Point Tractor & Trailer Inspection Process:**

- Procedures should be in place to verify the physical integrity of the trailer structure prior to stuffing, to include the reliability of the locking mechanisms of the doors.
- Border crossing tractors & trailers should be inspected upon arrival at the domestic facility.
- A 17-point Tractor & Trailer Inspection Process is recommended for all trucks and trailers arriving from foreign.











#### 17-Point Tractor & Trailer Inspection

- 1. Bumper
- 2. Engine
- 3. Tires (truck & trailer)
- 4. Floor
- 5. Fuel Tanks
- 6. Cab/ Storage Compartments
- 7. Air Tanks
- 8. Drive Shafts
- 9. Fifth Wheel

- 10. Outside/ Undercarriage
- 11. Floor
- 12. Inside/ Outside Doors
- 13. Side Walls
- 14. Ceiling/Roof
- 15. Front Wall
- 16. Refrigerated Unit
- 17. Exhaust




17-Point Tractor & Trailer Inspection





17

**Point** 







# Container Inspection...

#### **Seal Verification and Inspection Process:**

 After seal(s), container, tractor and trailer pass all inspections, the container/trailer doors can be opened.
Seals should be kept for investigative purposes!













# Container Inspection...

#### **Inspection of Cargo:**

- A cursory inspection of cargo should be conducted when container/trailer doors are opened.
- If contraband is encountered, close container/trailer doors and contact a Supervisor. The Supervisor will contact the proper authorities and CBP.
- Overages or shortages of cargo should be documented and recorded. These records may be needed to conduct future investigations!







