

## Case Study: 17726 Sikalastic Roof Cladding Repair



**Value**  
£3,000



**Location**  
Heathrow airport, land side



**Contract Length**  
3 days



### Types of Work Involved:

Scaffolding / Liquid coating roofing

### The Task:

Repair roof to cabin office construction.

### The Problem:

Water ingress causing damage to internal fixtures and fittings.

### The Solution:

A scaffold was erected to provide access and safety rail to roof area.

The faulty roof area was then prepared by cleaning; in this case some cover trims as well. Sikalastic 618 was applied, firstly an embedment coat at 1.5L/m<sup>2</sup>. The Sika Re-mat reinforcing sheet was then dressed and allowed to cure.

Finally a top coat of Sikalastic was applied at 0.75L/m<sup>2</sup>.

THE JOBS FINISHED  
WHEN THE  
CLIENTS SATISFIED,  
NOT US.